

City of Charlotte Bid Results FY 2022 (July 1, 2021 to June 30, 2022)

Date: Aug 12, 2022

NCDOT Std. #	Item Description (per City of Charlotte CIC)	Unit	25th Percentile	Median	75th Percentile	n
848	4" Concrete Sidewalk or Pad	SY	\$41	\$45	\$54	109
846	2' 6" Concrete Curb and Gutter	LF	\$31	\$35	\$38	94
607	Milling Asphalt Pavement, 0.0" to 3.0"	SY	\$20	\$25	\$29	123
610	Asphalt Concrete Base Course, Type B 25.0C	TN	\$81	\$100	\$128	23
610	Asphalt Concrete Intermediate Course, Type I 19.0C	TN	\$90	\$110	\$125	41
610	Asphalt Concrete Surface Course, Type S 9.5C	TN	\$89	\$115	\$130	48
	Asphalt Concrete Course Averages of B, I, S	TN	\$87	\$108	\$128	
620	Asphalt Binder for Plant Mix	TN	\$458	\$550	\$610	53
310	15" R.C. Pipe Culverts, Class III	LF	\$75	\$100	\$119	85
310	18" R.C. Pipe Culverts, Class III	LF	\$86	\$122	\$125	62
310	24" R.C. Pipe Culverts, Class III	LF	\$88	\$117	\$129	38
310	30" R.C. Pipe Culverts, Class III	LF	\$98	\$125	\$131	22
838	Endwalls	CY	\$750	\$850	\$1,200	57
453	Wall, Gravity Retaining	SF	-	\$111	-	7
SP (CLDS 10.31)	Concrete Wheelchair/Accessible Ramps	SY	\$86	\$108	\$155	44
849	Concrete Wheelchair/Accessible Ramps *	EA	\$1,490	\$1,872	\$2,686	
848	6" Concrete Driveways **	SY	\$75	\$80	\$85	104
840	Masonry Drainage Structures	EA	\$1,500	\$1,730	\$1,850	144
840	Frame with Grate (all types)	EA	\$650	\$650	\$650	165
852	5" Monolithic Concrete Islands	SY	-	\$100	-	7
SP (CLDS 50.04)	Safety Rail, Metal CLDS 50.04	LF	\$50	\$60	\$74	22
226	Undercut Excavation	CY	\$53	\$61	\$94	27
230	Borrow excavation	CY	\$23	\$25	\$26	135
862	Steel Beam Guardrail	LF	-	\$62	-	5
862	Guardrail Anchor Units (all types)	EA	-	\$4,420	-	3

Notes:

Item description and units must match to be part of this report.

For retaining walls (#453), monolithic island (#852), guardrail (#862) and anchor units (#862) average unit prices are reported.

Jurisdictions are not required to use these unit prices. They are provided for comparison purposes only.

* Wheelchair ramps - Assumes 17.33 SY per ramp to convert cost to each (EA). Typical dimensions: 6'x26' (156 SF or 17.33 SY).

** Includes 10 results (n) for 6" Concrete Sidewalk